

SCHEDULE OF BID ITEMS



NFSR 150 REALIGNMENT ROAD NO. 150

Sanders County Road Department
In Cooperation with
Cabinet Ranger District
Kootenai National Forest



SCHEDULE OF ITEMS

ITEM NO.	DESCRIPTION	METH* OF MEAS.	PAY UNIT	EST. QTY.	UNIT PRICE	TOTAL PRICE
15101	Mobilization	LSQ	Lump Sum	1	\$	\$
15211	Construction Survey and Staking, Method I	LSQ	Lump Sum	1	\$	\$
20103	Clearing and Grubbing, Haul and Pile Waste on Restoration Area	LSQ	Lump Sum	1	\$	\$
20401	Roadway Excavation, Tolerance Class F, Compaction Method 2	CQ	Cubic Yard	20,800	\$	\$
20402	Excavation and Embankment of NFSR 150 (MP 2.63 to 4.87), Compaction Method 2	CQ	Cubic Yard	3,240	\$	\$
20403	Reshape & Roughen NFSR 150 to 8:1 Template (STA 21+60 to 34+60)	CQ	Linear Foot	1,300	\$	\$
25101	Placed Riprap, Class II	AQ	Cubic Yard	6	\$	\$
60201	24 Inch Corrugated Steel Culvert, Compaction Method F	LSQ	Lump Sum	120	\$	\$
62201E	Equipment Rental, Excavator	AQ	Hour	32	\$	\$
62201D	Equipment Rental, Dump Truck	AQ	Hour	4	\$	\$
62550	Turf Establishment	LSQ	Lump Sum	1	\$	\$

Total Bid : \$ _____

* Designated Method of Measurement:

DQ - Designed Quantities; AQ - Actual Quantities; LSQ - Lump Sum Quantities

Notes:

- 1) All equipment shall be washed and free of weed seeds prior to entering the job site. The equipment shall be inspected by the owner at the County Shop.
- 2) The above Schedule of Items represents the quantities required to complete the primary work identified on the Site Plan. Additional work has been identified on the Site Plan and the owner has to option to authorize that additional work. The owner reserves the right to increase or decrease the amount of gravel and hours for each item with no adjustment to the unit price.

DESCRIPTION/SPECIFICATIONS/STATEMENT OF WORK

Project Description and Location

- (a) Description of Work. This project involves clearing and grubbing, excavation and embankment, roadway obliteration, hauling and placing pit run aggregate, furnishing and installing culverts on NFSR 150 (Rock Creek). This contract requires furnishing equipment on a fully-operated basis, in good mechanical and operating condition. It shall be operated by competent operators experienced in performing road construction type of work required by this contract. The Contractor shall provide all equipment, operating supplies, operators, supervision, and support functions necessary to perform the required work required under this contract. The work will include but is not limited to preparing the subgrade, excavating and constructing, and other road related improvements. The Sanders County Road Manager and the Cabinet Ranger District Engineer will provide direction for all hourly work that will be performed.

***Note: The owner reserves the right to reject any operator that is not qualified or is not performing work to reasonable standards or achieving adequate production rates.**

All construction activities affecting live stream channels shall be performed between July 15th and September 1st or when stream channels are dry. A 124 permit is required prior to construction and shall be provided by the Owner. Contractor shall keep a copy of the permit at all times during live stream work.

The contractor will be responsible for construction signing and accommodating public traffic during construction including dust control. The contractor shall submit a traffic control plan prior to construction.

- (b) Project Location. The project is located East of Noxon, MT on NFSR 150 Rock Creek Road (See Site Plan).
- (c) Site Visit. No formal site visit is scheduled. Questions regarding the project may be directed to Jared Koskela, Cabinet RD, at (406) 546-5894 or Lee Smith, Sanders County Road Dept. (406) 827-3691.
- (d) Period of Performance. The successful bidder will be expected to complete the work during the performance period of **upon award to September 1, 2025.**

1.2 - STANDARD SPECIFICATIONS

"Standard Specifications For Construction of Roads and Bridges on Federal Highway Projects" (FP-14, U.S. Customary Unit), are included in this solicitation by reference only. The requirements contained in these Specifications are hereby made a part of this solicitation and any resultant contract.

Copies of the "Standard Specifications For Construction of Roads and Bridges on Federal Highway Projects" (FP-14, U.S. Customary Unit), are available at <https://flh.fhwa.dot.gov/resources/specs/> .

1.3 - SUPPLEMENTAL SPECIFICATIONS

The attached Special Project Specifications are applicable to this contract.